BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18591/CALL-2

APPROVED SCHEDULE - B

EE/B[illegible]P/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Maintainence and Emergency works in Ward No .7, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Manjunath A		
				In Figures		In Words
1	360	Earthwork and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing of the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50m and all lifts	cum	104	37440.00	Rupees One Hundred Four Only
2	360	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	cum	73.57	26485.20	Rupees Seventy Three and Fifty Seven Paise Only
3	140	Supply of Water through water tanker to immersion Tank	day	350	49000.00	Rupees Three Hundred Fifty Only
4	400	HOM for pumping of 3.5 KL / Hr capacity pump (Page No. XXXXVI, Sl. No. 49 SR 2015-16	hr	50	20000.00	Rupees Fifty Only
5	172.5	KSRRB 2-1.1 : Earthwork excavation in Ornary soil for leveling and Lowring the ground manually (other than foundation of Buildings culverts road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5 m excavated surface leveled and nearly dressed disposed earth to be leveled after breaking clods and neatly dressed as per specifications. specification no KBS 2.1(a) 2.3.1 pg no. 5 / Item no., 2.1/PWD SR 2015-16	cum	156.88	27061.80	Rupees One Hundred Fifty Six and Eighty Eight Paise Only
6	14.5	Supplying and Spreading Stonedust for the Exsisting surface to fix Shamiyana etc. (Page No. II, Item No. 50) 2014-15 SR	cum	750	10875.00	Rupees Seven Hundred Fifty Only
7	14.4	Providing and Fixing flex board and caution boards for the publics to take suitable precautions	no	200	2880.00	Rupees Two Hundred Only
8	750	Hire Charges for Armless Plastic Chairs	no	4	3000.00	Rupees Four Only
9	120	Hire Charges for Steel Table of Size 6'x4'	day	40	4800.00	Rupees Forty Only
10	520	Hire charges for supplying and running circuit service main with sheathed aluminium wire and insulators	no	12	6240.00	Rupees Twelve Only
11	11	Hire charges for Providing Mike system including amplyfire sound box, etc. for anouncement to take suitable precuationary measures	no	1200	13200.00	Rupees One Thousand Two Hundred Only
12	300	Hire Charges for Shamiyana Side Wall of 8ft light (Size ss x 200 Ft = 220 Rft)	Rft	5	1500.00	Rupees Five Only
13	3000	Hire charges for Shamiyana with necessary Bamo Poles Erection Charges including transportation	Rft	15	45000.00	Rupees Fifteen Only
14	750	Hire charges for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 Sqm PVC insulted and sheathedaluminium wire (KPWD SR 2015-16 P. 55/I 6 ii b)	Rft	10	7500.00	Rupees Ten Only
15	128	Hire charges for Flood lighting Arrangements for the stage and existing Immersion Tank during night time	no	285	36480.00	Rupees Two Hundred Eighty Five Only
16	4500	Hire charges for Shamiyana with necessary Bamboo Poles Erection Charges including transportation	sft	14	63000.00	Rupees Fourteen Only
17	7200	Hire Charges for Shamiyana Side Wall of 9ft light (Size 8 x 15 Ft = 120Sft) for 15 days	sft	5	36000.00	Rupees Five Only
18	375	Engaging unskilled heavy Mazdoor labour for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the Pooja Time pg no L.11, sl no 05, 2015-16	no	243.55	91331.25	Rupees Two Hundred Forty Three and Fifty Five Paise Only
19	36	Hire charges for Providing Flood lights for the stage	no	285	10260.00	Rupees Two Hundred Eighty Five Only
20	120	1321 Hire Charges of 100KVA Generator including opertator, Fule, Transportation and Handling charges (PWD SR 2015-16) (P. XXXXIX/ Item 92)	hr	630	75600.00	Rupees Six Hundred Thirty Only

5/9/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Manjunath A		
				In Figures		In Words
21	135	Hire charges for Providing Flood lights for the Existing Immersion tank for immersion the lord Ganesh Idols During Night time	no	285	38475.00	Rupees Two Hundred Eighty Five Only
22	360	Earthwork and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing of the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50m and all lifts	cum	104	37440.00	Rupees One Hundred Four Only
23	360	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	cum	73.57	26485.20	Rupees Seventy Three and Fifty Seven Paise Only
24	68	Supply of Water through water tanker to immersion Tank	no	350	23800.00	Rupees Three Hundred Fifty Only
25	90.72	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2015-16	cum	192.24	17440.01	Rupees One Hundred Ninety Two and Twenty Four Paise Only
26	15.12	KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.3) SR-2015-16	cum	5070.6	76667.47	Rupees Five Thousand Seventy and Sixty Paise Only
27	40.32	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 23, I.No. 5.6) SR-2015-16	Sqm	4135.32	166736.10	Rupees Four Thousand One Hundred Thirty Five and Thirty Two Paise Only
28	58.72	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P 15, I.No 4.28) SR-2015-16	Sqm	244.08	14332.38	Rupees Two Hundred Forty Four and Eight Paise Only
29	44.42	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.48 SR 2015-.16	cum	6332.04	281269.22	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
30	3.17	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 17, I.No. 4.46.2) SR-2015-16	Qtl	68900	218413.00	Rupees Sixty Eight Thousand Nine Hundred Only

5/9/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Manjunath A		
				In Figures		In Words
31	33.6	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.112.I.No. 15.3) SR-2015-16	sqm	75	2520.00	Rupees Seventy Five Only
					1471231.63	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/8/16

05/08